



	<b>8" CMU BLOCK WALL</b>														
66	8" CMU Block Wall	4125	10%	4537	SF		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
	<b>Material Required</b>														
67	16"x8"x8" CMU Blocks	4639	10%	5103	BLOCKS		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
68	Bags of Mortars	135	10%	149	BAGS		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
69	Sands	16	10%	18	SY		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
70	Wall Reinforcement (Ladder or Truss Type)	3078	10%	3386	LF		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
71	Block Fill	50	10%	55	CY		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
72	Zonolite	289	10%	318	BAGS		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
	<b>Concrete Masonary Units - Underground</b>														
	<b>8" Bond Beam</b>														
73	8" CMU Bond Beam	375	10%	413	LF		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
	<b>Material Required</b>														
74	16"x8"x8" CMU Blocks	422	10%	464	BLOCKS		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
75	Bags of Mortars	12	10%	14	BAGS		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
76	Sands	1	10%	2	SY		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
77	#5 Bars	560	10%	616	LF		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
78	Block Fill	5	10%	5	CY		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
79	Zonolite	26	10%	29	BAGS		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
	<b>Concrete Masonary Units - Dumpster</b>														
	<b>8" CMU BLOCK WALL</b>														
80	8" CMU Block Wall	249	10%	274	SF		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
	<b>Material Required</b>														
81	16"x8"x8" CMU Blocks	280	10%	308	BLOCKS		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
82	Bags of Mortars	8	10%	9	BAGS		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
83	Sands	1	10%	1	SY		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
84	Wall Reinforcement (Ladder or Truss Type)	186	10%	204	LF		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
85	Block Fill	3	10%	3	CY		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
86	Zonolite	17	10%	19	BAGS		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
	<b>Concrete Masonary Bond Beam</b>														
	<b>8" Bond Beam</b>														
87	8" CMU Bond Beam	450	10%	495	LF		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
	<b>Material Required</b>														
88	16"x8"x8" CMU Blocks	338	10%	371	BLOCKS		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
89	Bags of Mortars	15	10%	16	BAGS		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
90	Sands	2	10%	2	SY		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
91	#5 Bars	900	10%	990	LF		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
92	Block Fill	5	10%	6	CY		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
93	Zonolite	32	10%	35	BAGS		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
	<b>Concrete Masonary Bond Beam - Dumpster</b>														
	<b>8" Bond Beam</b>														
94	8" CMU Bond Beam	75	10%	83	LF		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
	<b>Material Required</b>														
95	16"x8"x8" CMU Blocks	56	10%	62	BLOCKS		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
96	Bags of Mortars	2	10%	3	BAGS		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
97	Sands	0	10%	0	SY		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
98	#5 Bars	150	10%	165	LF		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
99	Block Fill	1	10%	1	CY		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
100	Zonolite	5	10%	6	BAGS		\$0	Crew	D8	\$45		0	\$0	\$0.00	\$0
	<b>Subtotal (Masonry)</b>			<b>Total Material Cost:</b>			<b>\$0</b>	<b>Total Labor Cost:</b>			<b>\$0</b>				
	<b>\$0</b>														